

SOLAR PARK 1.5MW SKOUPA
Karyes, Lakonia, Greece



Project data

System name:	Skoupa
Operator:	Dodekanisos Eoliki AE
Energy company:	PPC
Commissioned:	January 2013
Location:	Karyes, prefecture of Lakonia
Completion time:	10 weeks

Technical data

Rated system power	1,497.96 kWp	No./type of modules	5,256 units Suntech STP285-24/Vd
Annual energy yield	2,157 MWh	Inverter	73 units Conext TL 20000E
Construction type	Ground-mounted	Tilt angle	25°
Orientation	South	Frame technology	HILTI